


Task 3c:

A Brief Description of The Architecture

Please watch DAY 9 video

You have been tasked to deploy the architecture below:



1. 2 EC2 instances
2. Node 1 should be preinstalled with NGINX
3. Node 2 should be preinstalled with Tomcat

4. Port 80 should be open on NGINX node
5. Port 8080 should be opened on Tomcat node

Requirements:

- Implement the architecture above
- IaC (Terraform) should be used to build the infrastructure
- Use Packer or Terraform templates to install Nginx/Tomcat
- Code should be saved in SCM